



CENTRAL UNIVERSITY OF HARYANA

(Established vide Act No. 25 (2009) of Parliament)
Jant-Pali, Mahendergarh-123029

NOTICE INVITING QUOTATION NO. 08/2023

Sealed percentage rate quotations are invited on behalf of Central University of Haryana, Mahendergarh. The quotation should reach the office of the Executive Engineer, Room No.-217, Administrative Building, CUH on or before 11/07/2023 upto 11:00 AM. The quotation shall be opened on the same day i.e. 11/07/2023 at 03:00 PM. The bidders may attend the said meeting on 11/07/2023.


Name of Work: Gypsum board partition in Room No.-212 and 230 for creation of lecture halls in Academic Block-1 at CUH.

Sr. No.	Description	Qty.	Unit	Rate	Amount
1	Providing and fixing partition up to ceiling height consisting of G.I. frame and required board, including providing and fixing of frame work made of special section power pressed/roll form G.I. sheet with zinc coating of 120 gms/sqm (both side inclusive), consisting of floor and ceiling channel 50mm wide having equal flanges of 32 mm and 0.50 mm thick, fixed to the floor and ceiling at the spacing of 610 mm centre to centre with dash fastener of 12.5 mm dia meter 50 mm length or suitable anchor fastener or metal screws with nylon plugs and the studs 48 mm wide having one flange of 34 mm and other flange 36 mm and 0.50 mm thick fixed vertically within flanges of floor and ceiling channel and placed at a spacing of 610 mm centre to centre by 6 mm dia bolts and nuts, including fixing of studs along both ends of partition fixed flush to wall with suitable anchor fastener or metal screws with nylon plugs at spacing of 450 mm centre to centre, and fixing of boards to both side of frame work by 25 mm long drywall screws on studs, floor and ceiling channels at the spacing of 300 mm centre to centre. The boards are to be fixed to the frame work with joints staggered to avoid through cracks, M.S. fixing channel of 99 mm width (0.9 mm thick having two flanges of 9.5 mm each) to be provided at the horizontal joints of two boards, fixed to the studs using metal to metal flat head screws, including jointing and finishing to a flush finish with recommended jointing compound, jointing tape, angle beads at corners (25 mm x 25 mm x 0.5 mm), joint finisher and two coats of primer suitable for board as per manufacture's specification and direction of engineer in charge all complete. 75 mm overall thickness partition with	78.00	Sqm.	1291.00	100698.00

	12.5 mm thick double skin fire rated Glass Reinforced Gypsum (GRG) plaster board conforming to IS: 2095: part 3 (Board with BIS certification marks)				
2	Wall painting with premium acrylic emulsion paint of interior grade, having VOC (Volatile Organic Compound) content less than 50 grams/ litre of approved brand and manufacture, including applying additional coats wherever required to achieve even shade and colour. Two coats	152.00	Sqm.	49.00	7448.00
3	Wall painting with premium acrylic emulsion paint of interior grade, having VOC (Volatile Organic Compound) content less than 50 grams/ litre of approved brand and manufacture, including applying additional coats wherever required to achieve even shade and colour. One coat	341.00	Sqm.	32.00	10912.00
	Total				1,19,058/-

Terms and Conditions:

1. The work will be carried out as per the satisfaction of the engineer in charge.
2. GST registration certificate of the agency is required to be enclosed along with quotation.
3. Validity of the quotations will be 60 days from the date of opening.
4. The rate includes all taxes like GST, and other taxes and carriage of the material etc.
5. Time of completion of work will be 20 days.
6. No advance payment will be made.
7. Conditional quotations will not be considered.
8. The agency should inspect the site before quoting the rate.
9. The quantity of items in BOQ is tentative which may change depending upon site conditions.
10. The CUH will not be responsible for any accident. The agency should provide proper safety tools to its workers.
11. Time is the main essence of the contract. Hence, an appropriate penalty upto 10% maximum can be imposed on the agency for delayed completion of work.
12. No labor below the age of 18 years be employed on site.
13. All T&P required will be arranged by the contractor.
14. The agency/Contractor shall make its own arrangement of electricity, if required.
15. Security deposit @5% and necessary recoveries i.e. GST, Labour Cess and Income Tax etc. will be recovered from the bills of the contractor.


04/10/23.
Executive Engineer